

KOLAR DIVISION.

Abstract Notification dated 28th November 1939.

The attention of the public is invited to the detailed notification, dated 28th November 1939, published on pages 2459-2462, Part VI of the *Mysore Gazette*, dated 7th December 1939, regarding tenders for improving the feeder channel to Devaramallur Major Tank, Reg. No. 32, Sidlaghatta Taluk.

The last date for lodging of tender is up to 2 P.M. on the 22nd December 1939.

Abstract Notification dated 3rd December 1939.

The attention of the public is invited to the detailed notification, dated 2nd December 1939, published on pages 2462-2464, Part VI of the *Mysore Gazette*, dated 7th December 1939, regarding tenders for restoring Korenahalli Malladepally Tank Reg. No. 250 in Srinivasapur Taluk.

The last date for receiving tenders is 22nd December 1939 up to 2 P.M.

C. R. IYENGAR,
Executive Engineer.

MANDYA DIVISION.

Notification dated 5th December 1939.

1. Sealed tenders will be received at the Office of the Executive Engineer, Mandya Division, up to 12 NOON on 2nd January 1940, for the restoration of Bettadahally Tank, Nagamangala Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Mandya Division, on payment of four annas per form, should be addressed to the Executive Engineer, Mandya Division, in a sealed cover and superscribed as "Tender for Restoration of Bettadahally Tank." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a deposit of Rs. 185 (Rupees one hundred and eighty-five only) paid to the Treasury to the credit of "17 (a) Deposits" against the account of the Executive Engineer, Mandya Division, Mandya. The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 2nd January 1940, at Mandya Division. The final acceptance of the tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental schedule contract form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay Specifications (1931) and also furnish a security deposit of Rs. 185 in addition to earnest money.

6. Failure to comply with the condition 5 above, or to agree to carry out the work in accordance with the specifications and agreements in force, will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Mandya, on all working days between 11 A.M. and 5 P.M.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page, noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer, on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of May 1940, failing which, the Executive Engineer may, at his discretion, levy a penalty of Rs. 5-0-0 per day, which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(a) The contractor should at his own cost—

- (1) Provide rods, stakes, ropes and labour required in setting out the works.
- (2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
- (3) Provide mortar mills, and sheds, to keep materials under cover and also for workmen.
- (4) Arrange for protecting work during inclement weather.
- (5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
- (6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
- (7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
- (8) Provide arrangements for pumping and baling of water from excavations and foundations, wherever and whenever necessary with his own pumping apparatus, including necessary leading drains, slump pits, etc.
- (9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract and give such persons the use of ordinary scaffolding and ladders.
- (10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary, provide for the same by insurance at the proper time.

Note.—(b) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

Abstract estimate for restoring Bettadahally Minor Tank, Nagamangala Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
	<i>I. Bund.</i>				Rs. a. p.
1	Clearing jungle including removal of roots, cutting grips, steps, trenches in old bund, etc.	L. S.			40 0 0

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs. a. p.
2	Excavating a puddle trench in the centre of the old bund and using the spoil for the rear portion of the bund with watering and consolidation ..	C.yd.	0 3 0	165	
3	Providing puddle wall with watering and consolidation (1½' above present bund level) ..	"	0 8 0	247	
4	Earthwork to bund with watering and consolidation and one furlong lead ..	"	0 5 0	3,825	
5	Removing and resetting old stone work with new jelly wherever necessary ..	L. S.	..	..	23 0 0
6	Gravel backing to revetment including watering and consolidation ..	C.yd.	0 8 0	83	
7	New stone revetment ..	"	1 6 0	411	
8	Turfing including watering till the grass comes up ..	Sqr.	0 8 0	248.5	
9	Providing and fixing bund grade stones with bed slabs including carving figures, painting, etc. ..	Each	2 8 0	10	
10	Removing and refixing old grade stone with bed slab, carving and painting ..	"	0 12 0	1	
11	Supplying and fixing index stones with bed slabs ..	"	0 6 0	11	
12	Supplying and fixing Register No. stone including bed slab figuring, painting, etc., complete with date ..	"	5 0 0	1	
13	Supplying and fixing B. M. stones as per design ..	"	3 0 0	2	
14	Supplying and fixing gauge stones including carving, painting, etc., as per design ..	"	15 0 0	1	
<i>II. Sluice.</i>					
1	Excavating foundations, cutting bund and refitting, etc. ..	L. S.	..	..	
2	Stone jelly concrete in surki mortar ..	C.ft.	0 4 0	157	
3	Size stone in surki mortar ..	"	0 5 6	431	
4	Burnt stone slabs 6" thick and dressed ..	S.ft.	0 8 0	82	
5	Cement concrete coping slab 1 : 2 : 4 ..	C.ft.	0 12 0	18	
6	Cement pointing ..	L. S.	..	..	10 0 0
7	Cutting holes in slabs each ..	Each	1 0 0	4	
8	Providing and fixing C. I. pipe including carting and water tight joints ..	R.ft.	2 4 0	24	
9	Providing wooden plug and rod with locking arrangements ..	Each	15 0 0	1	
10	Closing the old sluice ..	L. S.	..	..	25 0 0
<i>III. Waste Weir.</i>					
1	Earthwork excavation in various kinds of soils ..	C.yd.	0 4 0	48	
2	Stone jelly concrete in surki mortar ..	C.ft.	0 4 0	360	
3	Size stone in surki mortar ..	"	0 5 6	1,289	
4	Cement concrete coping ..	"	0 12 0	75	
5	Cement pointing ..	L. S.	..	..	25 0 0
6	Rough stone work, new ..	C.yd.	1 6 0	148	
7	Filling scours with rough stone ..	"	0 8 0	54	
8	Unforeseen charges ..	L. S.	..	..	33 0 0

Notification dated 9th December 1939.

1. Sealed tenders will be received at the Office of the Executive Engineer, Mandya Division, up to 12 noon on 3rd January 1940, for extending Municipal High School at Mandya.
2. Tenders in the prescribed form obtainable from the office of the Executive Engineer, Mandya Division, on payment of four annas, should be addressed to the Executive Engineer, Mandya Division, in a sealed cover and superscribed as "Tender for Extending Municipal High School at Mandya. The name of the tenderer should also be superscribed on the top of the cover.
3. Each tender must be accompanied by a deposit of Rs. 950 (Rupees nine hundred and fifty only) paid to the treasury to the credit of 17(a) Deposits against the account of Executive Engineer, Mandya Division. The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract. Such a deposit in cash will not carry any interest.
4. The tenders will be opened in the presence of such tenderers who wish to be present on 3rd January 1940 at Mandya Division. The final acceptance of the tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.
5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental Schedule Contract Form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay Specifications (1931) and also furnish a security deposit of Rs. 950 in addition to earnest money.
6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force, will entail forfeiture of the earnest money.
7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.
8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Mandya, on all working days between 11 A.M. and 5 P.M.
9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.
10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.
11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.
12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.
13. No reference should be made to the Public Works Department schedule of rates.
14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.
15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.
16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.
17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of June 1940, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 5 per day which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.
18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.
19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(a) The contractor should at his own cost—

- (1) Provide rods, stakes, ropes and labour required in setting out the works.
- (2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
- (3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
- (4) Arrange for protecting work during inclement weather.
- (5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parabs, shoring, strutting and other requisite protective appliances during the progress of the work.
- (6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
- (7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
- (8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
- (9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
- (10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by insurance at the proper time.

Note.—(b) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

General abstract estimate for constructing a wing in the Western side in the rear of the existing Building of Municipal High School at Mandya.

No.	Items of work	Unit	Quantity	Rate
				Rs. a. p.
1	Earthwork excavation for foundation	C.yd.	65	0 5 0
2	Granite jelly concrete in lime mortar	C.ft.	591	0 4 0
3	Size stone in mud for foundation	"	892½	0 4 0
4	Size stone in mud with bond stones 6' apart including dressing neatly all quoins to 2" wide, etc., complete for basement	C.ft.	709	0 4 6
5	Burnt stone slab 6" thick, dressed and fixed over the retaining wall of verandah	S.ft.	85½	0 12 0
6	Cement concrete slab over the basement of inner walls for 1st course of superstructure	C.ft.	73½	0 12 0
7	Burnt brick in mud superstructure	"	2,427	0 3 3
8	Burnt stone slabs lintels and bearing 6" thick, rough dressed over all doors and windows and for bottom of girders as per deductions under item No. 7	S.ft.	285	0 9 0
9	Partition wall with ordinary burnt bricks in cement mortar 4½" thick with exmet reinforcement in every 3rd course including plastering with lime mortar and white-washing, etc., complete	"	234	0 8 0
10	Providing rolled steel girders of British Standard Specifications Tata's tested or Dorman Long's make including hoisting and fixing in position with cement concrete in walls, one coat of anti-corrosive paint and boxing with cement mortar and terrace bricks and reinforced with galvanised steel tex laid from above and plastering with finely ground mortar, etc., complete	Cwt.	51.85	16 0 0

No.	Items of work	Unit	Quantity	Rate
				Rs. a. p.
11	Roofing with R.C.C. cement concrete to consist of granite batani jelly (1 : 2 : 4) with necessary reinforcements for spans varying from 5' to 10' for the usual roof loads as per specifications including kappi in quick lime minimum thickness 3" with the usual slope for draining water and two courses of flat tiles in chunum mortar on top and plastering top and bottom and terrace with finely ground lime mortar and two coats of bitumen emulsion on top and white washing to ceiling including all scaffolding and centering charges, etc., complete	Sqr.	15.68	70 0 0
12	Teakwood doors with frames $3\frac{1}{2}" \times 5"$ and without bottom sills shutters $1\frac{1}{2}"$ thick $\frac{3}{4}"$ panelled and $\frac{1}{4}"$ glazed in the top and with 3 sets of steel butt hinges including necessary iron clamps and fittings, etc., complete	S.ft.	63	1 12 0
13	T.W. windows with frames $3\frac{1}{2}" \times 5"$ shutters $1\frac{1}{2}"$ thick, with $\frac{3}{4}"$ diameter iron bars placed 3" apart vertically with necessary fittings, etc., complete	S.ft.	180	2 0 0
14	T.W. rectangular ventilators with frames $3" \times 4"$ cross iron bars $\frac{3}{4}"$ diameter, shutters $1\frac{1}{4}"$ thick, fixed with ground glasses. $\frac{1}{8}"$ thick of approved quality necessary rings, ropes, pivots and iron fixtures, etc., complete	S.ft.	90	1 8 0
15	Flooring with cement concrete $1\frac{1}{2}"$ thick with granite batani jelly 1 : 2 : 4 on 4" of lime concrete with granite jelly and $\frac{1}{2}"$ cement plastering with topping of red coloured water proofed cement $\frac{1}{8}"$ thick and finished with ironite $2\frac{1}{2}$ lbs., per square and cut to required size of panels or tiles whatever required including asphalt expansion joints 6' apart and rounding of all corners, etc., complete	Sqr.	13.50	25 0 0
16	Plastering with chunam mortar for brick walls after raking up all the joints including rounding of all projecting and rounding corners with cement mortar 1 : 4 for a width of 3" on both sides, etc., complete	Sqr.	37.64	3 8 0
17	White and colour washing, two coats complete area as per plastering	Sqr.	37.64	0 4 6
18	R.C.C. chajja over windows	R.ft.	120	1 0 0
19	Deep cement pointing to basement (with cement mortar 1 : 3) and cutting lines including raking up the joints 1" deep, etc., complete	Sqr.	2.89	3 8 0
20	Providing reinforced cement concrete round pillars with granite batani jelly (1 : 2 : 4) and with necessary reinforcements for the verandah 10' high 13" diameter at bottom tapering to 11" at top including base, capitals and necessary fluting and ornamentations and plastering with finely ground lime mortar, etc., complete as per design to be furnished	Each	5	25 0 0
21	Parapet wall with burnt brick in lime mortar $1\frac{1}{2}'$ to 2' high, 9" thick including receding off sets at top and plastering and white washing, etc., including balustrades at 10' apart complete as per design around	R.ft.	213 $\frac{1}{2}$	1 4 0
22	Coving for ceiling with 5 or 6 off sets with finely ground lime mortar including rounding at corners with cement mortar, etc., complete as per design to be furnished around	R.ft.	456	0 5 0
23	Unforeseen charges	L. S.		114 0 0

Adding a verandah in the rear of the old and newly constructed building.

1	Earthwork excavation for foundation	C.yd.	59	0 5 0
2	Granite jelly concrete in lime mortar	C.ft.	537 $\frac{3}{4}$	0 4 0
3	Size stone in mud foundation	C.ft.	282	0 4 0
4	Size stone in mud basement	C.ft.	160	0 4 6

No.	Items of work	Unit	Quantity	Rate
				Rs. a. p.
5	Burnt stone slab over basement, 6" thick	S.ft.	106½	0 12 0
6	Providing R.C.C. pillars as per specification	Each	9	25 0 0
7	Providing R.S. Girders as per specification	Cwt.	13.94	16 0 0
8	Entablature wall brick in mud	C.ft.	264	0 3 3
9	Plastering the entablature wall	Sqr.	3.55	3 8 0
10	White and colour washing as per above	"	3.55	0 4 6
11	Roofing with R.C.C. as per specification	"	4.35	70 0 0
12	Flooring with cement concrete, etc. do	"	3.33	25 0 0
13	Coving for ceiling alround	R.ft.	71	0 5 0
14	Sundries	L. S.		27 0 0

Constructing a room by the side of the Head Master's Room in the old building.

1	Earthwork excavation for foundation	C.yd.	7	0 5 40
2	Stone jelly concrete in lime mortar	C.ft.	62	0 4 0
3	Size stone in mud for foundation	"	106	0 4 0
4	Size stone in mud for basement	"	87	0 4 6
5	R.C. slab over basement for 1st course of superstructure	"	11	0 11 0
6	Burnt brick in mud superstructure	C.ft.	356	0 3 3
7	Burnt stone lintels over windows and ventilators	S.ft.	30	0 9 0
8	Roofing with R.C.C. as per specification	Sqr.	1.36	70 0 0
9	T.W. windows as specified in the above estimate	S.ft.	30	2 0 0
10	T.W. ventilators do do	"	12	1 8 0
11	Flooring with cement concrete as per specification	Sqr.	1.03	25 0 0
12	Plastering with chunam mortar exterior and interior alround	"	5.51	3 8 0
13	White and colour washing as per specification	"	5.51	0 4 6
14	Cement pointing to basement alround	"	0.28	3 8 0
15	Parapet wall with burnt brick in mortar	R.ft.	14	1 0 0
16	Coving for ceiling as per above	"	20½	0 5 0
17	Sundries	L. S.		12 0 0
18	R.C.C. chajja over windows	S.ft.	15	1 0 0

Extending the Out-houses in the rear of High School.

1	Earthwork excavation for foundations	C.yd.	116	0 5 0
2	Stone jelly concrete in lime mortar	C.ft.	1,060½	0 4 0
3	Size stone in mud for foundation	"	1,680	0 4 6
4	Size stone in mud for basement	"	1,190	0 4 0
5	Burnt slab 6" thick for basement	S.ft.	187	0 12 0
6	Burnt brick in mud for superstructure	C.ft.	3,620	0 3 3
7	Burnt stone lintels for doors and girders <i>vide</i> deductions under item No. 6	S.ft.	146	0 9 0
8	T.W. wrought and put up	C.ft.	75	4 8 0
9	R.S. girders for verandah, (double)	Cwt.	24	16 0 0
10	Roofing with R.C.C. for verandah	Sqr.	7.35	70 0 0
11	Roofing with Mangalore tiles on teak reepers	"	15.25	24 0 0
12	Ridging with Mangalore tiles set in cement mortar	R.ft.	71½	0 8 0
13	Providing and fixing T.W. doors as per specifications	S.ft.	136½	1 12 0
14	Do windows do	"	142	2 0 0
15	Do ventilators do	"	14	1 8 0
16	Flooring with cement concrete as per specification	Sqr.	15.35	25 0 0
17	Plastering with chunam mortar	"	60.57	3 8 0
18	White and colour washing as per above	"	60.57	0 4 6
19	Deep cement pointing to basement	"	4.81	3 8 0
20	Providing R.C.C. round pillars 9' high	No.	12	25 0 0
21	Parapet wall with burnt brick in mortar	R.ft.	134½	1 0 0
22	Coving for ceiling length alround	"	267	0 5 0
23	Cornice work length alround	"	320	0 8 0
24	Painting doors and windows	L. S.		50 0 0
25	Sundry charges	"		45 0 0

Constructing compound wall in the rear of the High School Building at Mandya.

No.	Items of work	Unit	Quantity	Rate		
				Rs.	a.	p.
1	Earthwork excavation for foundations	C.yd.	13	0	5	0
2	Burnt stone in mud foundation	C.ft.	171	0	4	0
3	Burnt stone jelly concrete in mortar	C.ft.	140	0	4	0
4	Burnt stone in mud, basement	"	215	0	4	6
5	Burnt stone slabs 6" thick for sills of gate, etc.	S.ft.	30	0	9	0
6	Superstructure—Burnt brick in mud	C.ft.	266	0	3	3
7	Chunum plastering	Sqr.	2·97	3	8	0
8	White and colour washing as per plastering	"	2·97	0	4	6
9	Cement pointing to basement	R.ft.	89	3	8	0
10	Coping over the compound wall in mortar including plastering, etc., complete	R.ft.	50	0	4	0
11	Providing a T.W. gate as per specification	S.ft.	40	1	8	0
12	Providing a T.W. door as per specification	"	23	1	12	0
13	Providing gate pillars (burnt brick in cement mortar) as per specification	No.	2	25	0	0
14	Sundry and other items of work	L. S.		21	0	0

K. V. KARVE,
Executive Engineer.

HASSAN DIVISION.

Notification dated 9th December 1939.

Sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, Hassan, up to 3 P.M., on Monday the 31st December 1939 for constructing (1) A female ward and connecting corridor to connect Maternity ward and new female ward, (2) A connecting corridor to connect Maternity and Out-patient ward, (3) One block of nurses quarters, (4) A Septic ward, (5) A portico to Sri Chamarajendra Hospital at Hassan.

2. Tenders in the prescribed form obtainable in the Office of the Executive Engineer, Hassan Division, Hassan, should be addressed to the Executive Engineer, Hassan Division, Hassan, and should be superscribed as "Tender for constructing (1) A female ward and connecting corridor to connect Maternity ward and new female ward, (2) A connecting corridor to connect maternity and out-patient ward, (3) One block of nurses quarters, (4) A Septic ward, (5) A portico to Sri Chamarajendra Hospital at Hassan." The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender must be accompanied by a deposit of Rs. 490, Rs. 230, Rs. 163, Rs. 140, Rs. 38 respectively in cash as earnest money. The earnest money of the successful tenderer will be retained as cash security for the due fulfilment of the contract. (Cash amount will not carry any interest). In case of the acceptance of the tender, an addition of the five per cent of the estimated amount as security deposit should be paid at the time of executing the agreement in the Public Works Department.

4. The tenders will be opened in the presence of such tenderers who wish to be present on the date of opening. The final acceptance of the tenders will rest with the Superintending Engineer, Shimoga Circle, who does not bind himself to accept the lowest or any tender, or to assign any reasons whatever for the rejection of any.

5. The name of the successful tenderers will be posted on the Notice Board in the Office of the Executive Engineer in due course. Within eight days of the acceptance of the tenders, the successful tenderers will be required to execute the agreements in the departmental schedule contract forms, for the due fulfilment of the contracts.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. Copies of contract documents, estimates and drawings may be seen at any time at the Office of the Executive Engineer, Hassan Division, Hassan, on all working days between 11 A.M. and 5 P.M.

8. Specific rates should be given for each item in the schedule and the rates should be in rupees, annas and pies and expressed in words and figures.

9. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates tendered should include all such lumpsum items.

10. No alterations which are made by the tenderers in the contract documents in the nomenclature of the sanctioned sub-heads will be recognised and if corrections are made, the tenders will be liable to rejection.

11. There should be no corrections or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.